

BILANS ROBÓT ZIEMNYCH – ŚCIEŻKA						
Pikieta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Całk. obj. wykopu	Całk. obj. nasypu
0+000.00	0.01	5.15	0.00	0.00	0.00	0.00
0+007.86	0.18	8.14	0.80	52.77	0.80	52.77
0+013.14	0.40	8.95	1.53	45.06	2.34	97.83
0+016.69	0.33	12.90	0.57	39.21	2.90	137.04
0+060.00	0.25	6.00	0.00	0.00	2.90	137.04
0+070.00	1.21	2.62	7.26	43.11	10,17	180.15
0+080.00	1.44	6.78	13.21	47.04	23,37	227.19
0+087.47	1.35	7.17	10.39	52.09	33.76	279.28
0+090.00	1.28	6.89	3.50	17.06	37.26	296.34
0+096.68	0.85	7.06	7.51	44.93	44.77	341.27
0+100.00	0.78	7.23	2.72	23.70	47.49	364.97
0+110.00	0.36	6.61	5.70	69.18	53.19	434.15
0+120.00	0.31	5.86	3.32	62.34	56.21	496.49
0+140.00	6.72	2.71	70.31	85.67	126.82	582.16
0+150.00	6.42	1.66	66.14	22.23	192.96	604.39
0+160.00	5.51	1.00	59.94	13.42	252.90	617.81
0+170.00	4.03	0.35	46.84	6.58	299.74	624.39
0+180.00	3.28	0.27	35.72	3.04	335.46	627.43
0+190.00	3.85	0.29	35.62	2.80	371.08	630.23
0+211.00	4.15	0.43	84.05	7.56	455.12	637.79
0+220.00	3.57	0.22	34.74	2.94	489.87	640.73
0+230.00	3.26	0.22	34.14	2.19	524.01	642.92
0+240.00	3.01	0.12	31.44	1.70	555.45	644.62
0+250.00	3.16	0.06	31.22	0.90	586.67	645.52
0+260.00	3.94	0.00	35.50	0.31	622.17	645.83
0+270.00	2.35	0.00	31.45	0.00	653.62	645.83
0+280.00	2.38	0.00	23.67	0.00	677.29	645.83
0+290.00	2.25	0.00	23.16	0.00	700.45	645.83
0+300.00	2.67	0.00	24.61	0.00	725.06	645.83
0+316.69	3.44	0.00	51.12	0.00	776.18	645.83
0+320.00	3.31	0.00	10.98	0.00	787.16	645.83
0+330.00	2.65	0.00	29.77	0.00	816.93	645.83
0+340.00	1.97	0.00	23.10	0.00	840.03	645.83
0+350.00	1.28	0.04	16.26	0.22	856.29	646.05
0+360.00	0.97	0.12	11.26	0.83	867.55	646.88
0+370.00	0.44	0.18	7.03	1.50	874.58	648.38
0+380.00	0.11	0.21	2.71	1.95	877.29	650.33
0+390.00	0.91	0.05	5.05	1.30	882.34	651.63
0+397.41	1,54	0.07	9.08	0.46	891.42	652.09

wiadukt  
- r. ziemne wg.  
b. mostowej