

Lp.	Podstawa	Opis i wyliczenia	j.m.	Poszcz.	Razem
Roboty budowlane					
1		BUDOWA KLATKI ZEW. PRZEDSIONKA, RAMPY - D59			
1.1		Roboty malarskie.CPV 45442100-8			
1.1.	NNRNKB 1 202 1134- 0202	Gruntowanie podłóży, powierzchnie pionowe, preparatem Atlas Uni Grunt (5,7*13,68*2)+(2,6*13,68*2)<kl ściany> 5,82*2*2,53 (2,45+5,46+5,46+4,5+9,8)*2,89 [45*2*2,51-(30*0,9*2,0)-(1,8*2,1)]*4 <Korytarz I, II, III, IV p> 1,56*2,51*4<korytarz> 4,32*13,68*2<kl sch II> 3,1*13,68<kl sch II> [(7,39+2,28+2,28+2,25)*2,51]*5	m ² m ² m ² m ² m ² m ² m ²	 227,088 29,449 79,966 672,480 15,662 118,195 42,408 178,210	
				RAZEM	1363,46
1.1.	NNRNKB 2 202 1134- 0102	Gruntowanie podłóży, powierzchnie poziome, preparatem Atlas Uni Grunt 3,29*4,15<001> 45,36*1,56*4<i,II,III,IV p> 7,39*2,28<kl II> 3,1*4,32*5<kl II> 28,16*1,55<parter> 5,7*2,6*5<kl I sufit>	m ² m ² m ² m ² m ²	 13,654 283,046 16,849 66,960 43,648	
				RAZEM	424,16
1.1.	KNR 2-02 3 1505-01	Malowanie farbami lateksowymi wewnątrznych tynków gładkich bez gruntowania, 2-krotne poz.1.1.1+poz.1.1.2	m ² m ²	 1787,620	
				RAZEM	1787,62
1.1.	KNR-W 4- 4 01 1216-01	Zabezpieczenie podłóg folią poz.1.1.2+(30*0,9*2,0*4)<drzwi>	m ² m ²	 640,160	
				RAZEM	640,16
1.1.	KNR 2-02 r. 5 16 z.sz.5.15	Czas pracy rusztowań grupy 1 (poz.:1.1.3)	m-g		
				RAZEM	162,475
1.1.	KNR 2-02 6 1505-01	Lakierowanie ścian (lamperia) [45*2*1,5-(30*0,9*1,5)-(1,8*1,5)]*4 <Korytarz I, II, III, IV p> 5,82*2*1,50 (1,5*13,68*2)+(1,5*13,68*2)<kl ściany>	m ² m ² m ²	 367,200 17,460 82,080	
				RAZEM	466,74