

Budowa drogi leśnej nr DR/006 na terenie obrębu leśnego Marcule w Leśnictwach Seredzice i Polany km 2+600 – km 5+000

Tabela 4

Zestawienie robót ziemnych elementów konstrukcji drogi

Nazwa	km	km	Powierzchnia	Wykop	Nasyp	Wartość netto
			m ²	m ³	m ³	m ³
Odcinek 2	2+ 600.00	3+ 300.00	6 246.71	670.00	846.66	-176.66
46-Z-23'			221.80	53.14	2.70	50.44
47-Z23			211.07	26.95	5.02	21.93
48-Z24			207.35	11.33	53.16	-41.83
49-Z24'			171.56	0.01	41.71	-41.70
50-Z25			199.48	7.61	30.01	-22.40
51-Z26			215.84	6.41	38.31	-31.90
52-Z27			213.58	17.85	18.81	-0.96
53-Z27'			226.94	9.72	50.83	-41.11
54-Z28			206.04	13.64	13.24	0.40
55-Z28"			221.15	48.21	12.03	36.18
56-SKŁADNICA 3			1 312.91	514.74	5.57	509.17
57-D8			431.08	73.63	3.10	70.53
58-Z28'			203.95	19.51	3.31	16.20
59-Z35'			193.97	48.32	1.95	46.37
Odcinek 3	3+ 300.00	4+ 296.02	10 264.32	1 035.15	1 735.79	-700.64
60-Z35			198.53	22.42	3.40	19.02
61-Z37			231.27	17.39	6.93	10.46
62-Z36'			229.89	32.41	20.12	12.29
63-Z36			277.72	21.11	30.44	-9.33
64-D9 +38			853.02	8.99	364.93	-355.94
65-Z29			382.13	36.87	27.97	8.90
66-Z30			355.02	8.99	72.59	-63.60
67-PZ2	4+ 296.02	4+ 346.75	1 058.06	55.42	227.69	-172.27
68-SKŁADNICA 4			738.48	18.39	144.35	-125.96
Odcinek 4	4+ 346.75	4+ 740.00	3 802.94	236.13	782.74	-546.61
69-Z39			198.21	5.37	46.28	-40.91
70-Z32			194.08	6.54	21.00	-14.46
71-Z33			205.04	24.45	12.74	11.71
72-Z34			229.28	12.82	42.13	-29.31
Odcinek 5	4+ 740.00	5+ 000.00	2 330.62	119.70	589.63	-469.93
SUMA			32 032.04	3 183.22	5 255.14	-2 071.92
Suma wykopy				3 183.22		

Wykopy do wykorzystania na miejscu				3 183.22		
Wykopy do wywieżenia				0.00		
Nasyp z wykopu					3 183.22	
Nasyp do dowieżenia					2 071.92	